


Date: Thursday, 07/02/2008 10:32:29 AM
 User: Linda Lacelle

Process Sheet

Customer :	CU-DAR001 Dart Helicopters Services	Drawing Name :	PLUG
Job Number :	37289		
Estimate Number :	13092		
P.O. Number :		Part Number :	D3492051
This Issue :	07/02/2008	Drawing Number :	D3492 REV C
Prsht Rev. :	NC	Project Number :	N/A
First Issue :	//	Drawing Revision :	C
Previous Run :		Material :	
Written By :		Due Date :	14/02/2008
Checked & Approved By :		Qty:	20
Comment :	Est Rev:A New Issue 06-06-20 JLM Est Rev:B as per Rev C 07-12-06 DD	Um:	4 Each

Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
----------------	------------------------------	----------------------

1.0	M6061T6R0875	6061-T6 Round Bar .875"
-----	--------------	-------------------------



Comment: Qty.: ~~0.0035 f(s)~~ Unit Total: ~~0.0139 f(s)~~ *each* *060" 7/10/08-02-11*
 6061-T6 Round Bar .875"
 (M6061T6R0875)
 Batch: *M7950*

J.F. 08/02/09

2.0	HARDINGE	HARDINGE CNC LATHE SMALL
-----	----------	--------------------------

**Comment:** HARDINGE CNC LATHE SMALL

1-Turn as per Folio FA714 & Dwg D3492
 Dwg Rev: _____
 Folio Rev: _____

J.F. 08/02/09 (26)

3.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--

**Comment:** INSPECT PARTS AS THEY COME OFF MACHINE

J.F. 08/02/09 (28)

4.0	QC8	SECOND CHECK
-----	-----	--------------

**Comment:** SECOND CHECK

R9 08/02/10

5.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
-----	-------------	-------------------------------

**Comment:** SMALL & MEDIUM FAB RESOURCE 1

1-Deburr

W/A/Am

Date: Thursday, 07/02/2008 10:32:29 AM
User: Linda Lacelle

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: PLUG

Job Number: 37289

Part Number: D3492051

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: HAND FINISHING RESOURCE #1

Chemical Conversion Coat as per QSI 005 4.1

FL 08/02/11 (24)

7.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3
(Flat End Only)

FL 08/02/12 (24)

8.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT/CHEMICAL CONVERSION

08-02-12

(24)

9.0

NAS1611015

O-RING



Comment: Qty.: 1.0000 Each(s)/Unit Total: 4.0000 Each(s)

Qty Part Number Description Batch

1 NAS1611-015 O-RING 1A106043

08-02-12

(x 24)

10.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



Comment: Hand Finishing

2-Assemble O'Ring as per Dwg D3492 Applying some O'Ring Lube

A/R 55-O'Ring Lube Batch: M101223

FL 08-02-12 (x 24)

11.0

QC5

INSPECT WORK TO CURRENT STEP



Comment: INSPECT WORK TO CURRENT STEP

08/02/12 (x 24)

12.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

FL 08-02-12 (x 24)

13.0

QC21

FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

08 02 13


Job Completion



08-02-13

D3492-XX PLUG
(SEE TABLE)

NAS1611 PLUG
(SEE TABLE)



D3492-XXX PLUG PARTS LIST


QTY -041	QTY -043	QTY -045	QTY -047	QTY -049	QTY -051	QTY -053	PART NUMBER	DESCRIPTION
X							D3492-041	PLUG ASSEMBLY
	X						D3492-043	PLUG ASSEMBLY
		X					D3492-045	PLUG ASSEMBLY
			X				D3492-047	PLUG ASSEMBLY
				X			D3492-049	PLUG ASSEMBLY
					X		D3492-051	PLUG ASSEMBLY
						X	D3492-053	PLUG ASSEMBLY
1							D3492-1	PLUG
	1						D3492-3	PLUG
		1					D3492-5	PLUG
			1				D3492-7	PLUG
				1			D3492-9	PLUG
					1		D3492-11	PLUG
						1	D3492-13	PLUG
		1					NAS1611-005	O-RING
			1				NAS1611-007	O-RING
1							NAS1611-010	O-RING
						1	NAS1611-012	O-RING
	1						NAS1611-013	O-RING
					1		NAS1611-015	O-RING
				1			NAS1611-016	O-RING





NOTES:
1) O-RING: POSSIBLE SUPPLIER P/N: NAS1611-XXX OR PARKER 2-XXX

RELEASED
07.10.16


C	ADD -049/-051/-053, CHANGE DRAWING FORMAT	PH	07.10.05
B	ADD -047; UPDATE DIM A FOR -045	PH	06.05.11
A	NEW ISSUE	PH	06.01.04
REV.	DESCRIPTION	BY	DATE
DESIGN		DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
DRAWN			
CHECKED		DRAWING NO.	REV. C
MFG. APPR.		D3492	SHEET 1 OF 2
APPROVED		TITLE	SCALE
DE APPR.		PLUG	2:1
DATE	07.10.05	COPYRIGHT © 2007 BY DART AEROSPACE LTD THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.	



POWDER COAT THESE
FACES ONLY PER NOTE 2



D3492-XX PLUG



DETAIL D

D3492-XX PLUG MACHINING DETAILS

P/N	A	B	C	MATERIAL SPEC
D3492-1	0.625	0.394	0.055	M6061T6R0.625
D3492-3	0.750	0.582	0.045	M6061T6R0.750
D3492-5	0.375	0.188	0.045	M6061T6R0.375
D3492-7	0.500	0.270	0.045	M6061T6R0.500
D3492-9	0.938	0.750	0.045	M6061T6R1.000
D3492-11	0.850	0.664	0.045	M6061T6R0.875
D3492-13	0.750	0.520	0.045	M6061T6R0.750

NOTES:

- 1) MATERIAL: ALUMINUM 5052-H32 OR 6061-T6 OR 1100-0 PER QQ-A-225/7 (5052) OR QQ-A-225/8 (6061) OR QQ-A-200/8 (6061) OR QQ-A-225/1 (1100) (REF. DART MATERIAL SPEC M6061T6R0.000)
- 2) FINISH: CHEMICAL CONVERSION COAT PER DART QSI 005 4.1
POWDER COAT WHITE GLOSS (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES: PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) UNITS: INCHES UNLESS OTHERWISE NOTED
- 5) BREAK SHARP EDGES: 0.005 TO 0.010 MAX
- 6) IDENTIFICATION: N/A
- 7) WEIGHT: N/A

RELEASED
07.11.16

DESIGN		DART AEROSPACE LTD
DRAWN		HAWKESBURY, ONTARIO, CANADA
CHECKED		DRAWING NO. D3492 REV. C
MFG. APPR.		SHEET 2 OF 2
APPROVED		TITLE PLUG SCALE 4:1
DE APPR.		
DATE	07.10.05	

COPYRIGHT © 2007 BY DART AEROSPACE LTD
THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS
NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT
WRITTEN PERMISSION FROM DART AEROSPACE LTD.